

Please note:
-Glazing to be according to SANS10400 XA report
-All new and existing brick walls to receive new marmoran coating to later specification.

GENERAL NOTES:

- Contractor to verify all levels, heights, and site dimensions before putting any work to hand.
- Any discrepancies to be reported to the architect immediately for clarification.
- This drawing is not to be scaled - figured dimensions are to be used at all times.
- All work to be carried out in strict accordance with local authorities requirements, National Building Regulations SANS 10400 and other relevant SANS standards.
- This drawing is to be read in conjunction with all relevant consultants drawings, details, and specifications.
- All shop drawings are to be submitted for Architect's approval prior to manufacture or installation.
- Only the latest revision is to be used.
- All dimensions are given in millimeters.
- The Architect accepts no responsibility for errors resulting from the misinterpretation of this drawing.

© COPYRIGHT:

Please note that the copyright of the literary works, artistic works and published editions contained herein is vested with **EHH Architects Inc.** Any adaptation, distribution, sale or for hire, or any form of reproduction of these works - in any part or in their entirety, by any party other than **EHH Architects Inc.** is an infringement of this copyright, and **EHH Architects Inc.** reserves the right to claim damages from any party infringing this copyright, unless these rights are varied in writing.

REVISIONS:

REV: DATE: DESCRIPTION: BY:

SPECIFICATIONS

GENERAL:
steps - 150mm risers 250mm treads, all balustrading to be min 1000mm AFFL and to comply with sabs 10400, all stormwater to fall away from building to road, 32mm gpo connection laid to sabs 950/1969 - by telkom.

STRUCTURE:
All structure as per structural engineer's details. Lintels to not exceed 3m.

WALLS:
External walls - 280mm thick, walls to be plastered and painted to future spec. Internal walls - 110mm thick to be plastered and painted to spec.

FLOORS:
New floor slabs to be allow for 10mm finish on 40mm screed, finishes to later spec, all floor slabs to be to engineers design and detail.

WINDOWS:
All windows are to be aluminium window frames to architect's schedule, all glazing to comply with SABS 10400 part N1. All glazing larger than 1sqm or less than 500mm from FFL to be safety glazing.


ROOF:
Concrete flat roof to fall as indicated. All cantilevered concrete as per Engineer's design and detail. Waterproofed by specialist to Architect's approval

CEILING:
All ceilings are to be skimmed and painted suspended gypsum plasterboard, cornice to be as per Architect's future design detail. Cornice to be routed timber 19 x 22 mm Meranti to be painted to match colour of ceiling.

DRAINAGE: (where applicable)
100mm Ø sewer pipe with a minimum fall of 1:60, 100mm Ø stub vent at head of sewer drain pipe.
Rooding eyes (re) at head of drain, at all changes of direction, and at a maximum of 25m intervals, inspection eyes' (ie) at all junctions of drain, and to have marked covers at ground level.
All waste fittings to have 65mm re-seal traps, all waste pipes to be accessible over entire length for cleaning and repairs.
All waste pipes underground to be sleeved.
All drainage fixtures on first floor to be anti-siphoned
All soil fittings with a vertical discharge greater than 1220mm to have anti-siphon vent pipes (asyp).
Pipe sizes (Ø):
wc - 100mm
sink - 40mm
whb: 32mm
All drainage work to be carried out in accordance with the NBR, part 'P'
All drain pipes less than 450mm at invert level are to be protected as per part 'PP24' of the NBR.

PLEASE NOTE:

- All measurements of floor space are taken from the outside of the exterior walls
- Stairs and lift measured from the inside of brick walls
- First floor measurement excludes void
- Roof level not included in the calculations



Reg. no. 91/03020/21

tel: 021 461 1111 fax: 021 461 1111
email: info@ehh.co.za or sales@ehh.co.za
web: www.ehh.co.za
id: mid free

CLIENT:
Squareland Investment Trust

PROJECT:
136 Bree Street, Cape Town
ERF NO. 2730

DRAWING:
ELEVATIONS


SCALE: DATE:
1:100 15.10.2014

DRAWN: CHECKED:
DM RB


PROJECT NO: DRAWING NO: REVISION:
21328 AL 4-001 A

DRAWING STATUS:

COUNCIL SUBMISSION



SW Elevation
Scale 1:100



SE Elevation
Scale 1:100